

# EOS TPC Test Installation

---

**Peter Barnes**  
**Physics and Space Technology**  
**Lawrence Livermore National Laboratory**



FNAL, 29 September 2001

# TPC Test Installation Subjects

---



- **What is it?**
- **Cable Plant**
- **Interlocks and Clock**
- **Gas and High Voltage**
- **Operation Issues**
- **MC7 Installation Plans**
- **MTest Test Plans**


# What is the EOS TPC?



- **LBL designed/built ~'88-90**
  - 2 m<sup>3</sup> P10 gas volume
  - 150 x 96 x 75 cm<sup>3</sup> active
- **1.2 x 0.8 cm<sup>2</sup> pads**
  - 120 x 128 = 15,360 total
- **P10 @ atmosphere**
  - Anode wires ~1200 V
    - Gas gain ~3000
  - Drift voltage ~9000 V
    - Drift velocity ~5 cm/μs
    - Sampled @ 20 MHz




Used in LBL EOS; BNL E910, E895



# Electronics




## Low Voltage



## High Voltage



## Digital



## Stick



# Cabling Status

---




- **All racks in place in MTest**
- **All racks powered**
- **Cables installed:**
  - Low Voltage power
  - High Voltage for anodes and cathode
  - Bitbus slow control
  - CLK/TRG master and distribution
  - Interlock and status repeater
  - Fiber optic data readout
- **Still to do:**
  - Gating grid drivers (2)
  - Replace fiber optics with new jacketed cable? Getting price quote.



# Interlocks and Clock




- Low voltage interlocked
  - DC rack cooling air
  - TPC cooling water
  - CLK
- Rebuilt CLK/STRG module
- Installed water chiller and distribution



# Gas System



- Part of original system still exists.
- Preliminary Gas Safety Assessment:
  - P10 now deemed flammable.
  - MTest installation will be Class 0 (Lowest Risk)
    - Minimal hardware impact (vent line, signage, purge procedure, . . .)
- Plan to test P10 and P8 (non-flammable)
- Building temporary minimal system for Mtest



# Operation Issues

---



- **Current operation rules:**
  - Attended low voltage operation permitted
    - **NO UNATTENDED OPERATION** (custom cards not approved)
  - Flowing nitrogen (flammable gas not approved)
- **Gas and high voltage systems:**
  - In addition to static controls (signage, piping, vent, . . .)
  - Will require documented purge procedure and checklist.
  - Working for preliminary Operation Readiness Clearance in mid October.
    - Will allow P10 and high voltage.



# MC7 Installation Plans

---



- **Access to MC7 and Jolly Green Giant (JGG)**
  - Current downstream rollup door will be moved to upstream bump out.
    - *Provides access to upstream face of JJG magnet for TPC.*
  - Investigating use of E690 drift chamber rails for JGG as support rails for TPC in JGG
- **Gas**
  - Need to understand final (original EOS) gas system.
  - Analyze experiment gas loads as a whole.
- **Racks and electronics**
  - Need global understanding of detector front ends and rack requirements.

# MTest Test Plan

---



- **Identify working/spare/broken sticks and receiver cards**
- **Demonstrate that TPC “works”**
  - Show cosmic  $\mu$  tracks crossing the chamber.
  - Show most regions sensitive (modulo bad sticks)
- **Investigate P8 vs. P10**
- **Launch DAQ (re)development**